SHIMOGA DIVISION.

Dated 3rd March 1911.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 15th March 1911, for extending Civil Hospital, Shimoga, for the use of Female Dispensary. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of November 1911.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government promissory Notes, as earnest money, and be superscribed "Tender for extending Civil Hospital, Shimoga, for Female Dispensary" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of the probable cost of extending the Civil Hospital at Shimoga.

Items of work	*Per*	*Quantity*
Dismantling Mangalore tiled roof, etc.	Sqrs.	8·08
Roofing with new Mangalore tiles and teak reapers, etc., complete	Sqrs.	14·59
Do with old Mangalore tiles	"	8·08
Clearing site and levelling ground	Lump sum Rupees	
Earthwork excavation	C. yds.	92
Filling earth to basement level and tamping	"	125
Burnt stone in lime mortar	C. ft.	2612
Burnt brick in lime mortar	"	4033
Archwork, elliptical	"	59
Centering charges	Lump sum Rupees	
Burnt stone slabs, dressed and fixed	S. ft.	380
Plastering with lime mortar	Sqrs.	48·81
White and colour-washing	"	48·81
Pointing with lime mortar	"	2·88
Flooring with 1st class Mangalore tiles on 3" concrete bed and cement pointing.	"	9·58
Flooring with Marseilles tiles and cement pointing ...	"	1·30
Teakwood doors pannelled shutters with brass hinges, bolts, locks and self closing spring.	S. ft.	162
Teakwood windows glazed shutters with brass hinges, bolts, locks and self closing spring.	"	179
Teakwood windows half iron barred and half moving shutters ...	"	9
Removing the existing window and fixing in the extended building.	No.	5
Teakwood ventilators, glazed	S. ft.	16
Removing two small windows and fixing two big windows ...	Each	2
Dismantling wall and fixing small window and opening an arch way in passage room.	Lump sum Rupees	
Teakwood work, wrought and put up	C. ft.	198·3d
Dormer windows over roof	Each	5
Mangalore glass tiles	"	80
Teakwood eave board	R. ft.	50
Wood oiling	Sqrs.	20·94
Chocolate painting	"	7·14
Lime mortar plaster ceiling	"	8·18
Removing honey comb work and constructing wall with burnt brick in lime mortar.	C. ft.	104
Teakwood work wrought and put up for racks	"	28·32
Teakwood planks, 1" thick including fitting with screws ...	S. ft.	600
V-shaped drain with surki concrete and cement plastering ...	R. ft.	290
Constructing cistern	No.	2

FRANK A. STEELE,
Executive Engineer.